

# Work Order ID 93958

November-28-12 10:07:53 AM

*Persh*

**\*93958\***

Page 1

Item ID: D3650-1

Accept

**\*N900040100\***

Setup Start **\*NS1\***

Revision ID:

Stop **\*NS2\***

Item Name: Aft Panel

Start Date: 28/11/2012 Start Qty: 5.00

**\*5\***

Cust Item ID:

Required Date: 12/12/2012 Req'd Qty: 5.00

**\*5\***

Customer:

Reference:

Approvals: Process Plan: MLJ

Date: 12-11-28 Tooling:

Date:

Run Start **\*NR1\***

QC:

Date: SPC (Y/N):

Date:

Stop **\*NR2\***

Sequence ID/ Work Center ID	Operation Description	Set Up/ Run Hours	Tool ID	Tool #	Plan Code	Accept Qty	Reject Qty	Reject Number	Insp. Stamp
--------------------------------	--------------------------	----------------------	---------	--------	--------------	---------------	---------------	------------------	----------------

Draw Nbr

Revision Nbr

D3650

Rev E

100

0.00

**\*100\***

FLOW WATER JET

Waterjet

Memo

0.00

6 0 Jan 12-12-4

FLOW CNC Waterjet

1-Cut as per Dwg D3650 Dwg Rev: E Prog Rev: E 2-  
Deburr if necessary

304 .002

110

QC2- Inspect parts off machine FAI/FAIB

0.00

**\*110\***

QC

Memo

0.00

6 0 Jan 12-12-4

Quality Control

120

QC8- Inspect parts - second check

0.00

**\*120\***

QC

Memo

0.00

DAS  
15  
2-89  
12 12 04

6 0 Jan 12-12-4

Quality Control

NCR: Yes / No

**WORK ORDER NON-CONFORMANCE / UPDATE**

DQA: \_\_\_\_\_ Date: \_\_\_\_\_

QA Closed: \_\_\_\_\_ Date: \_\_\_\_\_

Work Order: _____  Part No. _____  NCR No. _____	<b>DISPOSITION</b>  Rework <input type="checkbox"/> Scrap <input type="checkbox"/> Use-as-is <input type="checkbox"/> Work Order Update <input type="checkbox"/>	<b>AGAINST DEPARTMENT/PROCESS</b>  <table style="width: 100%;"> <tr> <td>Skid-tube <input type="checkbox"/></td> <td>Crosstube <input type="checkbox"/></td> <td>Water Jet <input type="checkbox"/></td> <td>Engineering <input type="checkbox"/></td> </tr> <tr> <td>Machining <input type="checkbox"/></td> <td>Small Fab <input type="checkbox"/></td> <td>Prod. Eng. Coord. <input type="checkbox"/></td> <td>Quality <input type="checkbox"/></td> </tr> <tr> <td>Thermoforming <input type="checkbox"/></td> <td>Finishing <input type="checkbox"/></td> <td>Rec/Store/Packaging <input type="checkbox"/></td> <td>Other <input type="checkbox"/></td> </tr> <tr> <td>Large Fab <input type="checkbox"/></td> <td>Composite <input type="checkbox"/></td> <td>Supplier <input type="checkbox"/></td> <td></td> </tr> </table>	Skid-tube <input type="checkbox"/>	Crosstube <input type="checkbox"/>	Water Jet <input type="checkbox"/>	Engineering <input type="checkbox"/>	Machining <input type="checkbox"/>	Small Fab <input type="checkbox"/>	Prod. Eng. Coord. <input type="checkbox"/>	Quality <input type="checkbox"/>	Thermoforming <input type="checkbox"/>	Finishing <input type="checkbox"/>	Rec/Store/Packaging <input type="checkbox"/>	Other <input type="checkbox"/>	Large Fab <input type="checkbox"/>	Composite <input type="checkbox"/>	Supplier <input type="checkbox"/>	
Skid-tube <input type="checkbox"/>	Crosstube <input type="checkbox"/>	Water Jet <input type="checkbox"/>	Engineering <input type="checkbox"/>															
Machining <input type="checkbox"/>	Small Fab <input type="checkbox"/>	Prod. Eng. Coord. <input type="checkbox"/>	Quality <input type="checkbox"/>															
Thermoforming <input type="checkbox"/>	Finishing <input type="checkbox"/>	Rec/Store/Packaging <input type="checkbox"/>	Other <input type="checkbox"/>															
Large Fab <input type="checkbox"/>	Composite <input type="checkbox"/>	Supplier <input type="checkbox"/>																

Root Cause	Date	Step	Qty	Description of work order update or Non-conformance	Initial Chief Eng	Action Description	Sign & Date	Verification	QC Inspector
Doc/Data <input type="checkbox"/>									
Equip/Tooling <input type="checkbox"/>									
Operator <input type="checkbox"/>									
Material <input type="checkbox"/>									
Setup <input type="checkbox"/>									
Other <input type="checkbox"/>									
Process <input type="checkbox"/>									
Supplier <input type="checkbox"/>									
Training <input type="checkbox"/>									
Unapproved <input type="checkbox"/>									

**FAULT CATEGORY**

<b>Landing Gear</b> <input type="checkbox"/> Bending <input type="checkbox"/> Centre Not Concentric to O/S <input type="checkbox"/> Cracks <input type="checkbox"/> Crushed/Crimped <input type="checkbox"/> Cuffs <input type="checkbox"/> Heat Treat <input type="checkbox"/> Inspection Strip in Tube <input type="checkbox"/> Ripples in Bend <input type="checkbox"/> Torque Waves in Extrusion <input type="checkbox"/> Turning Sequence <input type="checkbox"/> Wave/Twist in Tube	<b>General</b> <input type="checkbox"/> Bend <input type="checkbox"/> BOM/Route <input type="checkbox"/> Broken/Damaged <input type="checkbox"/> Burrs <input type="checkbox"/> Contamination <input type="checkbox"/> Countersink <input type="checkbox"/> Cut Too Short <input type="checkbox"/> Drill Holes <input type="checkbox"/> Drawing <input type="checkbox"/> Finish <input type="checkbox"/> Folio	<input type="checkbox"/> Grain <input type="checkbox"/> Hardware <input type="checkbox"/> Inspection Incomplete <input type="checkbox"/> Instructions Incomplete/Unclear <input type="checkbox"/> Maintenance <input type="checkbox"/> Mislabeled <input type="checkbox"/> Misread <input type="checkbox"/> Offset <input type="checkbox"/> Out of Calibration <input type="checkbox"/> Out of Sequence <input type="checkbox"/> Outside Dimensions  <input type="checkbox"/> Ovalized <input type="checkbox"/> Over/Under tolerance <input type="checkbox"/> Part Incorrect <input type="checkbox"/> Part Lost/Missing <input type="checkbox"/> Part Moved <input type="checkbox"/> Positioned Wrong <input type="checkbox"/> Power Loss/Surge  <input type="checkbox"/> Pressure/Forced <input type="checkbox"/> Temperature/Cure <input type="checkbox"/> Weld <input type="checkbox"/> Wrong Stock Pulled  <input type="checkbox"/> Other
---	---	--

# Work Order ID 93958

November-28-12 10:07:53 AM

**\*93958\***

Page 2

Item ID: D3650-1

Accept

**\*N900040100\***

Setup Start **\*NS1\***

Revision ID:

Stop **\*NS2\***

Item Name: Aft Panel

Start Date: 28/11/2012 Start Qty: 5.00 **\*5\***

Cust Item ID:

Required Date: 12/12/2012 Req'd Qty: 5.00 **\*5\***

Customer:

Reference:

Approvals: Process Plan: \_\_\_\_\_ Date: \_\_\_\_\_ Tooling: \_\_\_\_\_ Date: \_\_\_\_\_ Run Start **\*NR1\***  
QC: \_\_\_\_\_ Date: \_\_\_\_\_ SPC (Y/N): \_\_\_\_\_ Date: \_\_\_\_\_ Stop **\*NR2\***

Sequence ID/ Work Center ID	Operation Description	Set Up/ Run Hours	Tool ID	Tool #	Plan Code	Accept Qty	Reject Qty	Reject Number	Insp. Stamp
130		0.00							
<b>*130*</b>	NC BRAKE					6			SD 12/12/05
Brake NC	Memo	0.00							
Brake NC	Form as per Dwg D3650								
140		0.00							
<b>*140*</b>	QC5- Inspect part completeness to step on W/O					6			
QC	Memo	0.00							
Quality Control									
150		0.00							
<b>*150*</b>	Small Fab					6x			GP 12/12/05
Small Fab	Memo	0.00							
Small Fab	Assemble as per dwg D3650								

NCR: Yes / No

**WORK ORDER NON-CONFORMANCE / UPDATE**

DQA: \_\_\_\_\_ Date: \_\_\_\_\_

QA Closed: \_\_\_\_\_ Date: \_\_\_\_\_

Work Order: _____  Part No. _____  NCR No. _____	<b>DISPOSITION</b>  Rework <input type="checkbox"/> Scrap <input type="checkbox"/> Use-as-is <input type="checkbox"/> Work Order Update <input type="checkbox"/>	<b>AGAINST DEPARTMENT/PROCESS</b>  <table style="width: 100%;"> <tr> <td>Skid-tube <input type="checkbox"/></td> <td>Crosstube <input type="checkbox"/></td> <td>Water Jet <input type="checkbox"/></td> <td>Engineering <input type="checkbox"/></td> </tr> <tr> <td>Machining <input type="checkbox"/></td> <td>Small Fab <input type="checkbox"/></td> <td>Prod. Eng. Coord. <input type="checkbox"/></td> <td>Quality <input type="checkbox"/></td> </tr> <tr> <td>Thermoforming <input type="checkbox"/></td> <td>Finishing <input type="checkbox"/></td> <td>Rec/Store/Packaging <input type="checkbox"/></td> <td>Other <input type="checkbox"/></td> </tr> <tr> <td>Large Fab <input type="checkbox"/></td> <td>Composite <input type="checkbox"/></td> <td>Supplier <input type="checkbox"/></td> <td></td> </tr> </table>	Skid-tube <input type="checkbox"/>	Crosstube <input type="checkbox"/>	Water Jet <input type="checkbox"/>	Engineering <input type="checkbox"/>	Machining <input type="checkbox"/>	Small Fab <input type="checkbox"/>	Prod. Eng. Coord. <input type="checkbox"/>	Quality <input type="checkbox"/>	Thermoforming <input type="checkbox"/>	Finishing <input type="checkbox"/>	Rec/Store/Packaging <input type="checkbox"/>	Other <input type="checkbox"/>	Large Fab <input type="checkbox"/>	Composite <input type="checkbox"/>	Supplier <input type="checkbox"/>	
Skid-tube <input type="checkbox"/>	Crosstube <input type="checkbox"/>	Water Jet <input type="checkbox"/>	Engineering <input type="checkbox"/>															
Machining <input type="checkbox"/>	Small Fab <input type="checkbox"/>	Prod. Eng. Coord. <input type="checkbox"/>	Quality <input type="checkbox"/>															
Thermoforming <input type="checkbox"/>	Finishing <input type="checkbox"/>	Rec/Store/Packaging <input type="checkbox"/>	Other <input type="checkbox"/>															
Large Fab <input type="checkbox"/>	Composite <input type="checkbox"/>	Supplier <input type="checkbox"/>																

Root Cause	Date	Step	Qty	Description of work order update or Non-conformance	Initial Chief Eng	Action Description	Sign & Date	Verification	QC Inspector
Doc/Data <input type="checkbox"/>									
Equip/Tooling <input type="checkbox"/>									
Operator <input type="checkbox"/>									
Material <input type="checkbox"/>									
Setup <input type="checkbox"/>									
Other <input type="checkbox"/>									
Process <input type="checkbox"/>									
Supplier <input type="checkbox"/>									
Training <input type="checkbox"/>									
Unapproved <input type="checkbox"/>									

**FAULT CATEGORY**

<b>Landing Gear</b> <input type="checkbox"/> Bending <input type="checkbox"/> Centre Not Concentric to O/S <input type="checkbox"/> Cracks <input type="checkbox"/> Crushed/Crimped <input type="checkbox"/> Cuffs <input type="checkbox"/> Heat Treat <input type="checkbox"/> Inspection Strip in Tube <input type="checkbox"/> Ripples in Bend <input type="checkbox"/> Torque Waves in Extrusion <input type="checkbox"/> Turning Sequence <input type="checkbox"/> Wave/Twist in Tube	<b>General</b> <input type="checkbox"/> Bend <input type="checkbox"/> BOM/Route <input type="checkbox"/> Broken/Damaged <input type="checkbox"/> Burrs <input type="checkbox"/> Contamination <input type="checkbox"/> Countersink <input type="checkbox"/> Cut Too Short <input type="checkbox"/> Drill Holes <input type="checkbox"/> Drawing <input type="checkbox"/> Finish <input type="checkbox"/> Folio	<input type="checkbox"/> Grain <input type="checkbox"/> Hardware <input type="checkbox"/> Inspection Incomplete <input type="checkbox"/> Instructions Incomplete/Unclear <input type="checkbox"/> Maintenance <input type="checkbox"/> Mislabeled <input type="checkbox"/> Misread <input type="checkbox"/> Offset <input type="checkbox"/> Out of Calibration <input type="checkbox"/> Out of Sequence <input type="checkbox"/> Outside Dimensions	<input type="checkbox"/> Ovalized <input type="checkbox"/> Over/Under tolerance <input type="checkbox"/> Part Incorrect <input type="checkbox"/> Part Lost/Missing <input type="checkbox"/> Part Moved <input type="checkbox"/> Positioned Wrong <input type="checkbox"/> Power Loss/Surge	<input type="checkbox"/> Pressure/Forced <input type="checkbox"/> Temperature/Cure <input type="checkbox"/> Weld <input type="checkbox"/> Wrong Stock Pulled <input type="checkbox"/> Other
---	---	---	--	---

# Work Order ID 93958

November-28-12 10:07:53 AM

**\*93958\***

Page 3

Item ID: D3650-1

Accept

**\*N900040100\***

Setup Start **\*NS1\***

Revision ID:

Stop **\*NS2\***

Item Name: Aft Panel

Start Date: 28/11/2012 Start Qty: 5.00

**\*5\***

Cust Item ID:

Required Date: 12/12/2012 Req'd Qty: 5.00

**\*5\***

Customer:

Reference:

Approvals:

Process Plan:

Date:

Tooling:

Date:

Run Start **\*NR1\***

QC:

Date:

SPC (Y/N):

Date:

Stop **\*NR2\***

Sequence ID/  
Work Center ID

Operation  
Description

Set Up/  
Run Hours

Tool ID

Tool #

Plan  
Code

Accept  
Qty

Reject  
Qty

Reject  
Number

Insp.  
Stamp

160

QC5- Inspect part completeness to step on W/O

0.00

**\*160\***

QC

Memo

0.00

12/12/06

Quality Control

6

170

Identify as per dwg & Stock Location: 169

0.00

**\*170\***

Packaging

Memo

0.00

Packaging

12/12/07

180

QC21- Final Inspection - Work Order Release

0.00

**\*180\***

QC

Memo

0.00

Quality Control

12/12/10

YMF 12-12-09

NCR: Yes / No

**WORK ORDER NON-CONFORMANCE / UPDATE**

DQA: \_\_\_\_\_ Date: \_\_\_\_\_

QA Closed: \_\_\_\_\_ Date: \_\_\_\_\_

Work Order: _____  Part No. _____  NCR No. _____	<b>DISPOSITION</b>  Rework <input type="checkbox"/> Scrap <input type="checkbox"/> Use-as-is <input type="checkbox"/> Work Order Update <input type="checkbox"/>	<b>AGAINST DEPARTMENT/PROCESS</b>  <table style="width: 100%;"> <tr> <td>Skid-tube <input type="checkbox"/></td> <td>Crosstube <input type="checkbox"/></td> <td>Water Jet <input type="checkbox"/></td> <td>Engineering <input type="checkbox"/></td> </tr> <tr> <td>Machining <input type="checkbox"/></td> <td>Small Fab <input type="checkbox"/></td> <td>Prod. Eng. Coord. <input type="checkbox"/></td> <td>Quality <input type="checkbox"/></td> </tr> <tr> <td>Thermoforming <input type="checkbox"/></td> <td>Finishing <input type="checkbox"/></td> <td>Rec/Store/Packaging <input type="checkbox"/></td> <td>Other <input type="checkbox"/></td> </tr> <tr> <td>Large Fab <input type="checkbox"/></td> <td>Composite <input type="checkbox"/></td> <td>Supplier <input type="checkbox"/></td> <td></td> </tr> </table>	Skid-tube <input type="checkbox"/>	Crosstube <input type="checkbox"/>	Water Jet <input type="checkbox"/>	Engineering <input type="checkbox"/>	Machining <input type="checkbox"/>	Small Fab <input type="checkbox"/>	Prod. Eng. Coord. <input type="checkbox"/>	Quality <input type="checkbox"/>	Thermoforming <input type="checkbox"/>	Finishing <input type="checkbox"/>	Rec/Store/Packaging <input type="checkbox"/>	Other <input type="checkbox"/>	Large Fab <input type="checkbox"/>	Composite <input type="checkbox"/>	Supplier <input type="checkbox"/>	
Skid-tube <input type="checkbox"/>	Crosstube <input type="checkbox"/>	Water Jet <input type="checkbox"/>	Engineering <input type="checkbox"/>															
Machining <input type="checkbox"/>	Small Fab <input type="checkbox"/>	Prod. Eng. Coord. <input type="checkbox"/>	Quality <input type="checkbox"/>															
Thermoforming <input type="checkbox"/>	Finishing <input type="checkbox"/>	Rec/Store/Packaging <input type="checkbox"/>	Other <input type="checkbox"/>															
Large Fab <input type="checkbox"/>	Composite <input type="checkbox"/>	Supplier <input type="checkbox"/>																

Root Cause	Date	Step	Qty	Description of work order update or Non-conformance	Initial Chief Eng	Action Description	Sign & Date	Verification	QC Inspector
Doc/Data <input type="checkbox"/>									
Equip/Tooling <input type="checkbox"/>									
Operator <input type="checkbox"/>									
Material <input type="checkbox"/>									
Setup <input type="checkbox"/>									
Other <input type="checkbox"/>									
Process <input type="checkbox"/>									
Supplier <input type="checkbox"/>									
Training <input type="checkbox"/>									
Unapproved <input type="checkbox"/>									

**FAULT CATEGORY**

<b>Landing Gear</b> <input type="checkbox"/> Bending <input type="checkbox"/> Centre Not Concentric to O/S <input type="checkbox"/> Cracks <input type="checkbox"/> Crushed/Crimped <input type="checkbox"/> Cuffs <input type="checkbox"/> Heat Treat <input type="checkbox"/> Inspection Strip in Tube <input type="checkbox"/> Ripples in Bend <input type="checkbox"/> Torque Waves in Extrusion <input type="checkbox"/> Turning Sequence <input type="checkbox"/> Wave/Twist in Tube	<b>General</b> <input type="checkbox"/> Bend <input type="checkbox"/> BOM/Route <input type="checkbox"/> Broken/Damaged <input type="checkbox"/> Burrs <input type="checkbox"/> Contamination <input type="checkbox"/> Countersink <input type="checkbox"/> Cut Too Short <input type="checkbox"/> Drill Holes <input type="checkbox"/> Drawing <input type="checkbox"/> Finish <input type="checkbox"/> Folio	<input type="checkbox"/> Grain <input type="checkbox"/> Hardware <input type="checkbox"/> Inspection Incomplete <input type="checkbox"/> Instructions Incomplete/Unclear <input type="checkbox"/> Maintenance <input type="checkbox"/> Mislabeled <input type="checkbox"/> Misread <input type="checkbox"/> Offset <input type="checkbox"/> Out of Calibration <input type="checkbox"/> Out of Sequence <input type="checkbox"/> Outside Dimensions
		<input type="checkbox"/> Ovalized <input type="checkbox"/> Over/Under tolerance <input type="checkbox"/> Part Incorrect <input type="checkbox"/> Part Lost/Missing <input type="checkbox"/> Part Moved <input type="checkbox"/> Positioned Wrong <input type="checkbox"/> Power Loss/Surge
		<input type="checkbox"/> Pressure/Forced <input type="checkbox"/> Temperature/Cure <input type="checkbox"/> Weld <input type="checkbox"/> Wrong Stock Pulled <input type="checkbox"/> Other

# Picklist Print

November-28-12 10:07:57 AM

Page 1  
*[Signature]*

Work Order ID: 93958

**\*93958\***

Parent Item: D3650-1

**\*D3650-1\***

Parent Item Name: Aft Panel

Start Date: 28/11/2012

Required Date: 12/12/2012

Start Qty: 5.00

Required Qty: 5.00

Comments: IPP Rev:A New Issue 07-09-27 DD verified by: EC  
IPP Rev:B ECN 1113P 08-01-22 DD verified by: EC  
IPP Rev:C ecn1162 08-04-02 DD verified by: EC

Component Item ID/ Item Name	Replacement Item ID	Mfg/ Purch	Bin Item	Primary Location	Last Location	Route Seq ID	Unit of Measure	Qty on Hand	Qty per Kit	Total Qty	Qty Issued	Date Issued	Status
<del>*MS21062-3K*</del> <b>*MS21062-3K*</b> Nut Plate		Purchased	No			100	Each	148.0000	3	15		<i>[Signature]</i> 12/12/05	
				<u>Location</u>				<u>Loc Qty</u>					
				ST302				14					
				109590				1					
				117343				13					
				ST317				134					
				122452				22		15			
				123021				12					
				123346				100		3			
M304S26GA		Purchased	No			150	sf	416.6700	1.583	8331579			
<b>*M304S26GA*</b> 304/316 0.018 SHEET										<i>[Stamp]</i> 8.4			
				<u>Location</u>				<u>Loc Qty</u>					
				MAT020				416.67					
				117798				35.06					
				122753				125.61		122753			
				123135				256					

*Jm 12-12-4*

NCR: Yes / No

**WORK ORDER NON-CONFORMANCE / UPDATE**

DQA: \_\_\_\_\_ Date: \_\_\_\_\_

QA Closed: \_\_\_\_\_ Date: \_\_\_\_\_

Work Order: _____  Part No. _____  NCR No. _____	<b>DISPOSITION</b>  Rework <input type="checkbox"/> Scrap <input type="checkbox"/> Use-as-is <input type="checkbox"/> Work Order Update <input type="checkbox"/>	<b>AGAINST DEPARTMENT/PROCESS</b>  <table style="width: 100%;"> <tr> <td>Skid-tube <input type="checkbox"/></td> <td>Crosstube <input type="checkbox"/></td> <td>Water Jet <input type="checkbox"/></td> <td>Engineering <input type="checkbox"/></td> </tr> <tr> <td>Machining <input type="checkbox"/></td> <td>Small Fab <input type="checkbox"/></td> <td>Prod. Eng. Coord. <input type="checkbox"/></td> <td>Quality <input type="checkbox"/></td> </tr> <tr> <td>Thermoforming <input type="checkbox"/></td> <td>Finishing <input type="checkbox"/></td> <td>Rec/Store/Packaging <input type="checkbox"/></td> <td>Other <input type="checkbox"/></td> </tr> <tr> <td>Large Fab <input type="checkbox"/></td> <td>Composite <input type="checkbox"/></td> <td>Supplier <input type="checkbox"/></td> <td></td> </tr> </table>	Skid-tube <input type="checkbox"/>	Crosstube <input type="checkbox"/>	Water Jet <input type="checkbox"/>	Engineering <input type="checkbox"/>	Machining <input type="checkbox"/>	Small Fab <input type="checkbox"/>	Prod. Eng. Coord. <input type="checkbox"/>	Quality <input type="checkbox"/>	Thermoforming <input type="checkbox"/>	Finishing <input type="checkbox"/>	Rec/Store/Packaging <input type="checkbox"/>	Other <input type="checkbox"/>	Large Fab <input type="checkbox"/>	Composite <input type="checkbox"/>	Supplier <input type="checkbox"/>	
Skid-tube <input type="checkbox"/>	Crosstube <input type="checkbox"/>	Water Jet <input type="checkbox"/>	Engineering <input type="checkbox"/>															
Machining <input type="checkbox"/>	Small Fab <input type="checkbox"/>	Prod. Eng. Coord. <input type="checkbox"/>	Quality <input type="checkbox"/>															
Thermoforming <input type="checkbox"/>	Finishing <input type="checkbox"/>	Rec/Store/Packaging <input type="checkbox"/>	Other <input type="checkbox"/>															
Large Fab <input type="checkbox"/>	Composite <input type="checkbox"/>	Supplier <input type="checkbox"/>																

Root Cause	Date	Step	Qty	Description of work order update or Non-conformance	Initial Chief Eng	Action Description	Sign & Date	Verification	QC Inspector
Doc/Data									
Equip/Tooling									
Operator									
Material									
Setup									
Other									
Process									
Supplier									
Training									
Unapproved									

**FAULT CATEGORY**

Landing Gear	General	Other
<input type="checkbox"/> Bending	<input type="checkbox"/> Bend	<input type="checkbox"/> Grain
<input type="checkbox"/> Centre Not Concentric to O/S	<input type="checkbox"/> BOM/Route	<input type="checkbox"/> Hardware
<input type="checkbox"/> Cracks	<input type="checkbox"/> Broken/Damaged	<input type="checkbox"/> Inspection Incomplete
<input type="checkbox"/> Crushed/Crimped	<input type="checkbox"/> Burrs	<input type="checkbox"/> Instructions Incomplete/Unclear
<input type="checkbox"/> Cuffs	<input type="checkbox"/> Contamination	<input type="checkbox"/> Maintenance
<input type="checkbox"/> Heat Treat	<input type="checkbox"/> Countersink	<input type="checkbox"/> Mislabeled
<input type="checkbox"/> Inspection Strip in Tube	<input type="checkbox"/> Cut Too Short	<input type="checkbox"/> Misread
<input type="checkbox"/> Ripples in Bend	<input type="checkbox"/> Drill Holes	<input type="checkbox"/> Offset
<input type="checkbox"/> Torque Waves in Extrusion	<input type="checkbox"/> Drawing	<input type="checkbox"/> Out of Calibration
<input type="checkbox"/> Turning Sequence	<input type="checkbox"/> Finish	<input type="checkbox"/> Out of Sequence
<input type="checkbox"/> Wave/Twist in Tube	<input type="checkbox"/> Folio	<input type="checkbox"/> Outside Dimensions
		<input type="checkbox"/> Ovalized
		<input type="checkbox"/> Over/Under tolerance
		<input type="checkbox"/> Part Incorrect
		<input type="checkbox"/> Part Lost/Missing
		<input type="checkbox"/> Part Moved
		<input type="checkbox"/> Positioned Wrong
		<input type="checkbox"/> Power Loss/Surge
		<input type="checkbox"/> Pressure/Forced
		<input type="checkbox"/> Temperature/Cure
		<input type="checkbox"/> Weld
		<input type="checkbox"/> Wrong Stock Pulled
		<input type="checkbox"/> Other



# Picklist Print

November-28-12 10:07:57 AM

Page 2

Work Order ID: 93958

Parent Item: D3650-1

Parent Item Name: Aft Panel

\*93958\*

\*D3650-1\*

Start Date: 28/11/2012

Required Date: 12/12/2012

Start Qty: 5.00

Required Qty: 5.00

~~MS20427M3-3~~

Purchased

No

150

Each

1.743.000

18

90

\*\*

\*MS20427M3-3\*

Rivet

Location

Loc Qty

Loc Code

GA

1588

123352

1588

ST335

155

120930

3

121114

140

123021

12

*EP 12/12/05*

108

~~MS21060-3K~~

Purchased

No

150

Each

246.0000

6

30

\*\*

\*MS21060-3K\*

Nut Plate

Location

Loc Qty

Loc Code

ST302

46

116857

17

117423

13

117977

15

118267

1

ST316

200

123168

200

*EP 12/12/05*

36

NCR: Yes / No

**WORK ORDER NON-CONFORMANCE / UPDATE**

DQA: \_\_\_\_\_ Date: \_\_\_\_\_

QA Closed: \_\_\_\_\_ Date: \_\_\_\_\_

Work Order: _____  Part No. _____  NCR No. _____	<b>DISPOSITION</b>  Rework <input type="checkbox"/> Scrap <input type="checkbox"/> Use-as-is <input type="checkbox"/> Work Order Update <input type="checkbox"/>	<b>AGAINST DEPARTMENT/PROCESS</b>  <table style="width: 100%;"> <tr> <td>Skid-tube <input type="checkbox"/></td> <td>Crosstube <input type="checkbox"/></td> <td>Water Jet <input type="checkbox"/></td> <td>Engineering <input type="checkbox"/></td> </tr> <tr> <td>Machining <input type="checkbox"/></td> <td>Small Fab <input type="checkbox"/></td> <td>Prod. Eng. Coord. <input type="checkbox"/></td> <td>Quality <input type="checkbox"/></td> </tr> <tr> <td>Thermoforming <input type="checkbox"/></td> <td>Finishing <input type="checkbox"/></td> <td>Rec/Store/Packaging <input type="checkbox"/></td> <td>Other <input type="checkbox"/></td> </tr> <tr> <td>Large Fab <input type="checkbox"/></td> <td>Composite <input type="checkbox"/></td> <td>Supplier <input type="checkbox"/></td> <td></td> </tr> </table>	Skid-tube <input type="checkbox"/>	Crosstube <input type="checkbox"/>	Water Jet <input type="checkbox"/>	Engineering <input type="checkbox"/>	Machining <input type="checkbox"/>	Small Fab <input type="checkbox"/>	Prod. Eng. Coord. <input type="checkbox"/>	Quality <input type="checkbox"/>	Thermoforming <input type="checkbox"/>	Finishing <input type="checkbox"/>	Rec/Store/Packaging <input type="checkbox"/>	Other <input type="checkbox"/>	Large Fab <input type="checkbox"/>	Composite <input type="checkbox"/>	Supplier <input type="checkbox"/>	
Skid-tube <input type="checkbox"/>	Crosstube <input type="checkbox"/>	Water Jet <input type="checkbox"/>	Engineering <input type="checkbox"/>															
Machining <input type="checkbox"/>	Small Fab <input type="checkbox"/>	Prod. Eng. Coord. <input type="checkbox"/>	Quality <input type="checkbox"/>															
Thermoforming <input type="checkbox"/>	Finishing <input type="checkbox"/>	Rec/Store/Packaging <input type="checkbox"/>	Other <input type="checkbox"/>															
Large Fab <input type="checkbox"/>	Composite <input type="checkbox"/>	Supplier <input type="checkbox"/>																

Root Cause	Date	Step	Qty	Description of work order update or Non-conformance	Initial Chief Eng	Action Description	Sign & Date	Verification	QC Inspector
Doc/Data <input type="checkbox"/>									
Equip/Tooling <input type="checkbox"/>									
Operator <input type="checkbox"/>									
Material <input type="checkbox"/>									
Setup <input type="checkbox"/>									
Other <input type="checkbox"/>									
Process <input type="checkbox"/>									
Supplier <input type="checkbox"/>									
Training <input type="checkbox"/>									
Unapproved <input type="checkbox"/>									

**FAULT CATEGORY**

<b>Landing Gear</b> <input type="checkbox"/> Bending <input type="checkbox"/> Centre Not Concentric to O/S <input type="checkbox"/> Cracks <input type="checkbox"/> Crushed/Crimped <input type="checkbox"/> Cuffs <input type="checkbox"/> Heat Treat <input type="checkbox"/> Inspection Strip in Tube <input type="checkbox"/> Ripples in Bend <input type="checkbox"/> Torque Waves in Extrusion <input type="checkbox"/> Turning Sequence <input type="checkbox"/> Wave/Twist in Tube	<b>General</b> <input type="checkbox"/> Bend <input type="checkbox"/> BOM/Route <input type="checkbox"/> Broken/Damaged <input type="checkbox"/> Burrs <input type="checkbox"/> Contamination <input type="checkbox"/> Countersink <input type="checkbox"/> Cut Too Short <input type="checkbox"/> Drill Holes <input type="checkbox"/> Drawing <input type="checkbox"/> Finish <input type="checkbox"/> Folio	<input type="checkbox"/> Grain <input type="checkbox"/> Hardware <input type="checkbox"/> Inspection Incomplete <input type="checkbox"/> Instructions Incomplete/Unclear <input type="checkbox"/> Maintenance <input type="checkbox"/> Mislabeled <input type="checkbox"/> Misread <input type="checkbox"/> Offset <input type="checkbox"/> Out of Calibration <input type="checkbox"/> Out of Sequence <input type="checkbox"/> Outside Dimensions
<input type="checkbox"/> Ovalized <input type="checkbox"/> Over/Under tolerance <input type="checkbox"/> Part Incorrect <input type="checkbox"/> Part Lost/Missing <input type="checkbox"/> Part Moved <input type="checkbox"/> Positioned Wrong <input type="checkbox"/> Power Loss/Surge		
<input type="checkbox"/> Pressure/Forced <input type="checkbox"/> Temperature/Cure <input type="checkbox"/> Weld <input type="checkbox"/> Wrong Stock Pulled <input type="checkbox"/> Other		

<b>DART AEROSPACE LTD</b>		<b>Work Order:</b>	93958
<b>Description:</b> Aft Panel		<b>Part Number:</b>	D3650-1
<b>Inspection Dwg:</b> D3650	<b>Rev:</b> DE 4.1	<b>Page 1 of 1</b>	


### FIRST ARTICLE INSPECTION CHECKLIST

Drawing Dimension	Tolerance	Actual Dimension	Accept	Reject	Method of Inspection	Comments
Ø0.098	+0.004/-0.001	0.100"	—		✓	Jm
Ø0.213	+0.005/-0.001	0.214"	—		✓	
Ø0.250	+0.005/-0.001	0.253"	—		✓	
0.25	+/-0.030	0.254"	—		✓	
0.344	+/-0.010	0.254" 0.342"	—		✓	
0.35	+/-0.030	0.357"	—		✓	
0.312	+/-0.010	0.317"	—		✓	
16.611	+/-0.010	16.611"	—		T	Jm
15.800	+/-0.010	15.800"	—		T	
3.950	+/-0.010	3.947"	—		✓	
2.019	+/-0.010	2.019"	—		✓	
4.026	+/-0.010	4.031"	—		✓	
6.126	+/-0.010	6.129"	—		✓	
8.226	+/-0.010	8.225"	—		✓	Produra
10.313	+/-0.010	10.320"	—		✓	
12.252	+/-0.010	12.252"	—		T	
17.583	+/-0.010	17.583"	—		T	
16.646	+/-0.010	16.646"	—		T	
2.256	+/-0.010	2.258"	—		✓	
7.183	+/-0.010	7.180"	—		✓	
9.551	+/-0.010	9.547" 9.552"	—		✓	
10.665	+/-0.010	10.665"	—		✓	
12.020	+/-0.010	12.020"	✓		✓	
0.018	+/-0.010	0.019"	—		✓ T	

<b>Measured by:</b> Jm	<b>Audited by:</b> DAS 15	<b>Preliminary Approval:</b>
<b>Date:</b> 12-12-4	<b>Date:</b> 12-12-04	<b>Date:</b>

Rev	Date	Change	Revised by	Approved
A	08.07.24	New Issue	KJ/DD	
B	09.06.15	Dimensions updated per Dwg Rev C	KJ	
C	12.09.26	Dimensions updated per Dwg Rev D	KJ	

QTY -041	PART NUMBER	DESCRIPTION
X	D3650-041	TUNNEL TOP PANEL ASSEMBLY
1	D3650-1	AFT PANEL
1	D3650-3	CENTER PANEL
1	D3650-5	FWD PANEL
8	AN3C-3A	BOLT
8	AN960C10	WASHER




**D3650-041 TUNNEL TOP PANEL ASSEMBLY**

**NOTES:**

- 1) MATERIAL: N/A
- 2) FINISH: N/A
- 3) TOLERANCES: PER DART QSI 018 UNLESS OTHERWISE NOTED
- 4) UNITS: INCHES UNLESS OTHERWISE NOTED
- 5) BREAK SHARP EDGES: N/A
- 6) IDENTIFICATION: NONE
- 7) WEIGHT: 4.3 lbs
- 8) TORQUE FASTENERS 15 TO 25 in-lb
- 9) SEAL ALL MATING SURFACES AND ALL GAPS USING PROSEAL 700 FIRE WALL SEALANT

STANDARD  
RETURN TO  
ENGINEERING  
UNCONTROLLED COPY  
SUBJECT TO AMENDMENTS  
WITHOUT NOTICE  
WORK ORDER  
NO. 9-3958 MJS  
12-11-28



**RELEASED**  
2012-10-09

E	REVISED D3650-3; 0.040 IN THICKNESS WAS 0.018. MINOR DIMENSIONAL CHANGES AS A RESULT.	MB	12.10.01
D	D3650-11 REPLACED WITH AN EMBOSS; PAGE 4 DELETED. D3650-3 BEND RELIEFS CHANGED TO TRIANGULAR SHAPE AT BOTH ENDS. D3650-3 HOLES CHANGED TO SLOTS. ALL NOTES UPDATED TO CONFORM TO QSI 043. TIGHTENED CUT TOLERANCES IN ALL FLAT PATTERNS. DEO D3650-C-1 INCORPORATED.	RP	12.08.12
C	REFORMATTED TO NEW STANDARDS; RELOCATED PART LIST (ZN D2-2); ADDED SECTION VIEW J-J & REVISE DIMENSIONS (ZN B7-5, C4-5); ADDED RECESS LOCATION & REVISED DIMENSIONS (ZN C6-6, D5-6); MS20519-4MS WAS CR3523-4-03 & NAS1149CN432R WAS AN960C4 (ZN D5-7, B5-7, B8-7).	RF	08.10.14
B	SHEETS 1, 2 & 7: UPDATED FASTENER QUANTITIES; UPDATED VIEWS SHEETS 3 & 8: REMOVED/RELOCATED HOLES; UPDATED VIEWS SHEET 4: 1.8 WAS 1.5; 1.0 WAS 0.8; UPDATED VIEW; ADDED NOTE 8 SHEET 5: REMOVED NOTE IN C6 & ASSOCIATED DIMS; UPDATED VIEWS SHEET 6: REMOVED/RELOCATED HOLES & ADDED CUTOUT TO D3650-3F; MOVED D3650-11-11F TO SHEET 9; ADDED DETAIL I SHEET 9: RELOCATED D3650-11-11F FROM SHEET 6; UPDATED DIMS OF D3650-11-11F	RF	08.01.07
A	NEW ISSUE	RF	07.11.07
REV.	DESCRIPTION	BY	DATE
DESIGN	RF		
DRAWN	MB		
CHECKED	RP		
MFG. APPR.	4		
APPROVED			
DE APPR.	4		
DATE	12.10.01		




**DART AEROSPACE LTD**  
HAWKESBURY, ONTARIO, CANADA

DRAWING NO. **D3650** REV. E  
SHEET 1 OF 8  
TITLE **TOP PANEL ASSEMBLY** SCALE  
NTS


COPYRIGHT © 2007 BY DART AEROSPACE LTD  
THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.

93950

QTY	PART NUMBER	DESCRIPTION
X	D3650-1	AFT PANEL
1	D3650-1B	AFT PANEL BENT PART
18	MS20427M3-3	RIVET
6	MS21060-3K	NUTPLATE
3	MS21062-3K	NUTPLATE



**D3650-1 AFT PANEL**




**D3650-1B AFT PANEL BENT PART**

- NOTES:
- 1) MATERIAL: MAKE FROM D3650-1F
  - 2) FINISH: NONE
  - 3) TOLERANCES: PER DART QSI 018 UNLESS OTHERWISE NOTED
  - 4) UNITS: INCHES UNLESS OTHERWISE NOTED
  - 5) BREAK SHARP EDGES: 0.005 TO 0.010 MAX
  - 6) IDENTIFICATION: NONE
  - 7) WEIGHT: 1.3 LBS






RELEASED  
2012-10-09

DESIGN	RF	<b>DART AEROSPACE LTD</b> HAWKESBURY, ONTARIO, CANADA	
DRAWN	RP		
CHECKED	RP	DRAWING NO. <b>D3650</b>	REV. E
MFG. APPR.	RP		SHEET 2 OF 8
APPROVED	RP	TITLE	SCALE
DE APPR.	RP	<b>TOP PANEL ASSEMBLY</b>	NTS
DATE	12.10.01	<small>COPYRIGHT © 2007 BY DART AEROSPACE LTD THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.</small>	

93958




**D3650-1F AFT PANEL (FLAT PATTERN)**




- NOTES:**
- 1) MATERIAL: AISI 304/316 STAINLESS STEEL 0.018 THICK (26 GAUGE) SHEET, PER MIL-S-5059 OR AMS 5513/5524 OR ASTM A240 OR ASME SA240 REF. DART SPEC. M304S26GA
  - 2) FINISH: NONE
  - 3) TOLERANCES: PER DART QSI 018 UNLESS OTHERWISE NOTED
  - 4) UNITS: INCHES UNLESS OTHERWISE NOTED
  - 5) BREAK SHARP EDGES: 0.005 TO 0.010 MAX
  - 6) IDENTIFICATION: NONE
  - 7) WEIGHT: 1.3 lbs

DESIGN	RF	<b>DART AEROSPACE LTD</b>	
DRAWN	RP	HAWKESBURY, ONTARIO, CANADA	
CHECKED	RP	DRAWING NO.	REV. E
MFG. APPR.	AW	<b>D3650</b>	SHEET 3 OF 8
APPROVED	MP	TITLE	SCALE
DE APPR.	MP	<b>TOP PANEL ASSEMBLY</b>	NTS
DATE	12.10.01	COPYRIGHT © 2007 BY DART AEROSPACE LTD THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR FOR DISSEMINATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD	




93958





**SECTION E-E** C5-4



**SECTION J-J** C4-4








**D3650-3 CENTER PANEL**



- NOTES:**
- 1) MATERIAL: MAKE FROM D3650-3F
  - 2) FINISH: NONE
  - 3) TOLERANCES: PER DART QSI 018 UNLESS OTHERWISE NOTED
  - 4) UNITS: INCHES UNLESS OTHERWISE NOTED
  - 5) BREAK SHARP EDGES: 0.005 TO 0.010 MAX.
  - 6) IDENTIFICATION: NONE
  - 7) WEIGHT: 1.98 lbs




DESIGN	RF	<b>DART AEROSPACE LTD</b>	
DRAWN	MB	HAWKESBURY, ONTARIO, CANADA	
CHECKED		DRAWING NO.	REV. E
MFG. APPR.		D3650	SHEET 4 OF 8
APPROVED		TITLE	SCALE
DE APPR.		TOP PANEL ASSEMBLY	NTS
DATE	12.10.01	COPYRIGHT © 2007 BY DART AEROSPACE LTD	
THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.			





93958



**D3650-3F CENTER PANEL (FLAT PATTERN)**

RELEASED  
2012-10-09

**NOTES:**

- 1) MATERIAL: AISI 304/316 STAINLESS STEEL 0.040 THICK (20 GAUGE) SHEET.  
PER MIL-S-5059 OR AMS 5513/5524 OR ASTM A240 OR ASME SA240  
REF. DART SPEC. M304S20GA
- 2) FINISH: NONE
- 3) TOLERANCES: PER DART QSI 018 UNLESS OTHERWISE NOTED
- 4) UNITS: INCHES UNLESS OTHERWISE NOTED
- 5) BREAK SHARP EDGES: 0.005 TO 0.010 MAX
- 6) IDENTIFICATION: NONE
- 7) WEIGHT: 1.98 lbs


DESIGN		RF		DART AEROSPACE LTD	
DRAWN		MB		HAWKESBURY, ONTARIO, CANADA	
CHECKED		[Signature]		DRAWING NO.	REV. E
MFG. APPR.		[Signature]		D3650	SHEET 5 OF 8
APPROVED		[Signature]		TITLE	SCALE
DE APPR.		[Signature]		TOP PANEL ASSEMBLY	NTS
DATE		12.10.01		COPYRIGHT © 2007 BY DART AEROSPACE LTD THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.	



93958



QTY	PART NUMBER	DESCRIPTION
5	D3650-5	FWD PANEL
1	D3650-5B	FWD PANEL BENT PART
1	D3650-7-8.19	SEAL
1	D3650-9	ANGLE
1	D3893-1	DOUBLER
12	NAS1149CN432R	WASHER
12	MS20615-4M5	RIVET
8	MS20427M3-3	RIVET
2	MS21060-3K	NUTPLATE
2	MS21062-3K	NUTPLATE

MS21062-3K NUTPLATE (1X)  
MS20427M3-3 RIVET (2X)  
2 PL




D3650-5B  
FWD PANEL  
BENT PART

MS21060-3K NUTPLATE (1X)  
MS20427M3-3 RIVET (2X)  
2 PL




**DETAIL F**  
CS-6



**D3650-5 FWD PANEL**

CENTRE D3650-7/9 ON D3650-5B &  
TRANSFER Ø0.129 HOLES  
FROM D3650-9 TO D3650-7 & D3650-5B  
AS SHOWN  
INSTALL  
MS20615-4M5 RIVET  
NAS1149CN432R WASHER  
12 PL



**D3650-5B FWD PANEL BENT PART**



RELEASED  
2012-10-09

- NOTES:
- 1) MATERIAL: MAKE FROM D3650-5F
  - 2) FINISH: NONE
  - 3) TOLERANCES: PER DART QSI 018 UNLESS OTHERWISE NOTED
  - 4) UNITS: INCHES UNLESS OTHERWISE NOTED
  - 5) BREAK SHARP EDGES: 0.005 TO 0.010 MAX
  - 6) IDENTIFICATION: NONE
  - 7) WEIGHT: 0.8 lbs


DESIGN	RF	<b>DART AEROSPACE LTD</b>	
DRAWN	RR	HAWKESBURY, ONTARIO, CANADA	
CHECKED	ST	DRAWING NO.	REV. E
MFG. APPR.	ST	D3650	SHEET 6 OF 8
APPROVED	ST	TITLE	SCALE
DE APPR.	ST	TOP PANEL ASSEMBLY	NTS
DATE	12.10.01	COPYRIGHT © 2007 BY DART AEROSPACE LTD THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COMMERCE WITHOUT THE WRITTEN PERMISSION FROM DART AEROSPACE LTD.	



93958



**DETAIL G** C5-7  
2 PL



**DETAIL H** B5-7  
2 PL

**D3650-5F FWD PANEL (FLAT PATTERN)**

**NOTES:**



- 1) MATERIAL: AISI 304/316 STAINLESS STEEL 0.018 THICK (26 GAUGE) SHEET, PER MIL-S-5059 OR AMS 5513/5524 OR ASTM A240 OR ASME SA240 REF. DART SPEC. M304S26GA
- 2) FINISH: NONE
- 3) TOLERANCES: PER DART QSI 018 UNLESS OTHERWISE NOTED
- 4) UNITS: INCHES UNLESS OTHERWISE NOTED
- 5) BREAK SHARP EDGES: 0.005 TO 0.010 MAX
- 6) IDENTIFICATION: NONE
- 7) WEIGHT: 0.6 lb

DESIGN	RF	<b>DART AEROSPACE LTD</b>	
DRAWN	RP	HAWKESBURY, ONTARIO, CANADA	
CHECKED		DRAWING NO.	REV. E
MFG. APPR.		<b>D3650</b>	SHEET 7 OF 8
APPROVED		TITLE	SCALE
DE APPR.		<b>TOP PANEL ASSEMBLY</b>	NTS
DATE	12.10.01	COPYRIGHT © 2017 BY DART AEROSPACE LTD THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.	

RELEASE  
2012-10-09




93950




**D3650-7-8.19 SEAL**

**NOTES:**

- 1) MATERIAL: P/N 8168-1 TADPOLE SEAL (REF. BELL P/N 120-104-1)  
POSSIBLE SUPPLIER: EAGLE COPTERS OR BELL
- 2) FINISH: NONE
- 3) TOLERANCES: PER DART QSI 018 UNLESS OTHERWISE NOTED
- 4) UNITS: INCHES UNLESS OTHERWISE NOTED
- 5) BREAK SHARP EDGES: 0.005 TO 0.010 MAX
- 6) IDENTIFICATION: NONE
- 7) WEIGHT: 0.05 lb
- 8) PART NUMBER: D3650-7-X.XX  
WHERE X.XX = LENGTH IN INCHES  
EG. 12.50" LONG = D3650-7-12.50



**D3650-9 ANGLE**  
(MAKE FROM D3650-9F)



**D3650-9F ANGLE (FLAT PATTERN)**

**D3650-9F**

- 1) MATERIAL: AISI 304/316 STAINLESS STEEL 0.018 THICK (26 GAUGE) SHEET,  
PER MIL-S-5059 OR AMS 5513/5524 OR ASTM A240 OR ASME SA240  
REF. DART SPEC. M304S26GA
- 2) FINISH: NONE
- 3) TOLERANCES: PER DART QSI 018 UNLESS OTHERWISE NOTED
- 4) UNITS: INCHES UNLESS OTHERWISE NOTED
- 5) BREAK SHARP EDGES: 0.005 TO 0.010 MAX
- 6) IDENTIFICATION: NONE
- 7) WEIGHT: 0.05 lb

RELEASED  
2012-10-09

DESIGN	RF	DART AEROSPACE LTD	
DRAWN	RP	HAWKESBURY, ONTARIO, CANADA	
CHECKED		DRAWING NO.	REV. E
MFG. APPR.		D3650	SHEET 8 OF 8
APPROVED		TITLE	SCALE
DE APPR.		TOP PANEL ASSEMBLY	NTS
DATE	12.10.01	COPYRIGHT © 2007 BY DART AEROSPACE LTD THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.	